8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate showing the quantities for improving and extending the Anglo-Vernacular School at Kunigal.

No.	Items of work	Per	Quantity
1	Earthwork excavation and filling in basement	C. yd.	85
2	Burnt stone in mortar	C. ft.	613
3	Burnt brick in chunam	"	2,888
4	Arch work	"	118
5	Cut stone pillars with base and capitals	Each	16
6	Burnt stone slabs, dressed	S. ft.	545
7	Chunam plastering	Sq.	44·00
8	White and colour washing	"	110·00
9	Chunam pointing	"	2·65
10	Teakwood work wrought and put up with wood oiling	C. ft.	200·00
11	Roofing with 1st class Mangalore tiles on teak reepers	Sq.	26·00
12	Ridge tiles set in mortar	R. ft.	147
13	Cornic 9" thick	"	160
14	Zinc sheet for the valley with teak planks underneath	S. ft.	252
15	Teakwood doors panelled outer dimension	"	180
16	Teakwood windows outside panelled and inside glazed with iron bars, etc., complete	"	216
17	Glazed circular ventilators	"	14
18	Painting with silicate chocolate colour	Sqr.	23·00
19	Masonry finials	Each	6
20	Ventilating tiles	"	40
21	Teakwood sunshades	"	8
22	Removing windows marked A in hall and fixing new doors	"	2
23	Dismantling walls and fixing windows	"	4
24	Teakwood eave board 9" wide with wood oiling	R. ft.	140
25	Teak finials	Each	4
26	Teak terminals	"	8
27	Thin cornice over windows	R. ft.	292
28	Ornamental parapet wall	"	132
29	Flooring with Cuddapah slab over 3" concrete and cement pointing	Sq.	15·60
30	Dismantling and removing porch	Each	2
31	Unforeseen jobs if found necessary during execution	Lump sum	
32	Clearing site and levelling ground all round the school	"	
33	Gravelling ground around the school 7 yards wide	C. yd.	132
34	Stone brackets including fixing	No.	12

N. G. KRISHNA IYENGAR,
Offg. Executive Engineer.

MYSORE HEAD QUARTER RANGE.

Notice is hereby given that sealed tenders will be received at the office of the Assistant Engineer, Head Quarter Range, Mysore, up to 5 P.M. on the 5th March 1918, for dismantling the Band Room and constructing a new Car Shed at the South Gate of Fort, Mysore.

An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed in about six months after commencement.

2. The plans, detailed estimates and specifications may be seen at the office of the Assistant Engineer, Head Quarter Range, Mysore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted in the prescribed printed forms which may be obtained from the Assistant Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items will be executed.

4. Indefinite remarks against item such "as per estimate" "as per data", etc., will not be considered.

5. Each tender must be accompanied by a deposit of Rs. 500 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tenders for dismantling the Band Room and constructing a new Car Shed at the South Gate of Fort, Mysore," as the case may be, and in default of which, tenders will be rejected.

6. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

7. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

8. The name of the successful competitor, will be posted on the notice board in the Assistant Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

9. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

No.	Particulars of work	Per	Quantity
1	Dismantling brick in mortar wall	C. ft.	1,981
2	Removing teakwood joists	No.	22
3	Removing doors and windows	"	8
4	Do stone slabs	C. ft.	77
5	Lowering the basement and surrounding of Guard room including carting	C. yd.	92
6	Carting	Carts	176
7	Dismantling the Fort wall including brick masonry, stone facing and carting	C. yd.	1,395
8	Earthwork excavation	"	111
9	Do for filling including carting	"	6
10	Concrete in chunam	C. ft.	779
11	Burnt brick in chunam foundation, basement and superstructure	"	10,517
12	Do do arch work	"	312
13	Burnt stone slabs 6" thick highly dressed	S. ft.	284
14	Plastering with chunam with 2 coats finely finished	Sqr.	99·23
15	White and colourwashing	"	99·23
16	Teakwood windows with panel shutters and iron bars, fixing, hinges, etc., complete	S. ft.	512
17	Teakwood glazed fanlights, complete	"	100
18	Pukka terracing	Sqr.	22·06
19	Cornice with string course, complete	R. ft.	226
20	Stone brackets with Cuddapah slab lovey projection plastered over complete	"	36
21	Stone brackets, large, in front of entrance	No.	2
22	Brick masonry parapet ornamental with plastering top cornice, etc., complete	R. ft.	215
23	Masonry finial or kiosk over front pillars	No.	2
24	Masonry prabhavali with ornamental work as per elevation	"	1
25	Ornamental work for front pillars	"	Lump sum
26	Masonry finials	"	17
27	Steel girders including hoisting, painting Ry. freight, etc., complete	Cwt.	35
28	Teakwood work wrought and put up	C. ft.	218·50
29	Silicate painting	Sqr.	12·24
30	Wood oiling	"	21·25
31	Stone flagging with mortar, pointing using old stones	C. ft.	2,040
32	Teakwood ornamental gate	S. ft.	198
	Dismantling the Band room.		
1	Dismantling the heavy masonry walls of Janasala	C. ft.	30,842
2	Do brick in mortar walls including boulders	"	11,609
3	Removing teakwood joists	No.	69
4	Removing and stocking the doors	"	8
5	Do do windows	"	2
6	Do couples of car shed	"	31
7	Do the thick reepers of zinc roof	R. ft.	924
9	Do the zinc sheet roof	Sqr.	25·84
8	Earthwork excavation and carting, including dismantling of foundation masonry	C. yd.	365
10	Carting	Cart	3,226

GURU RAO SIRSI,
Assistant Engineer.

MYSORE DIVISION.

NOTICE.

The attention of the public is invited to advertisement in detail published in the *Mysore Gazette* dated 7th February 1918, calling tenders for "Restoring Homma tank, Register No. 36 of Chamrajnagar Taluk."

P. SUBBA RAO,
For *Executive Engineer.*

HASSAN DIVISION.

Dated 2nd February 1918.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Hassan Division, up to the 7th March 1918, for constructing an additional block to the A.-V. School at Arkalgud. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of the 30th June 1919.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 150 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing an additional block to the A.-V. School at Arkalgud," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.